

MITSUBISHI CEMENT CORPORATION

CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 12/8/2016

ASTM designation: C 1157 – 11 for Type HE. Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 11/1/2016

To: 11/22/2016

Chemical Composition:	ASTM Limits	UBC Limits	Test Results
Silicon Dioxide (SiO ₂), %			19.5
Aluminum Oxide (Al ₂ O ₃), %			5.2
Ferric Oxide (Fe ₂ O ₃), %			1.1
Calcium Oxide (CaO), %			64.1
Magnesium Oxide (MgO), %			2.3
Sulfur Trioxide (SO ₃), %			3.0
Loss on Ignition, %		7.0 Max.	5.0
Insoluble Residue, %		1.5 Max.	0.6
Total Alkali (%Na ₂ O + 0.658 * %K ₂ O), %			0.39
Tricalcium Silicate (C ₃ S), [b] %			46
Tricalcium Aluminate (C ₃ A), [b] %			11
CO ₂ , %			5.0
Limestone, %	15 Max.		12.2
Limestone Purity, %		85 Min.	94
Free Lime, %			1.1
PHYSICAL RESULTS:			
Blaine Fineness Average (m²/kg)			539
325 Mesh (% Passing)			98.7
Autoclave Expansion (%)	0.80 Max.		0.06
Mortar Bar Expansion (%) October 2016	0.020 Max.		0.008
Time of Set Initial Vicat (minutes)	45 / 420 Min. /	Max	88
Air Content (% by Volume)	12 Max	22 Max.	7.3
Heat of Hydration (kJ/kg)	(a)		377
Color (L value)	(a)		78
Compressive Strength Test:	ASTM Limits MPA psi		MPA PSI
1 Day		Min.	22.1 3203
3 Day		Min.	32.1 4653
7 Day		··· 	36.4 5280
28 Day October 2016			42.8 6208

This cement has been sampled and tested in accordance with ASTM standard methods and procedures. All tests results are certified to comply with the type specification designated above. No other warranty is made or implied. We are not responsible for improper use or workmanship. [a] For information only. [b] Adjusted per ASTM C150 A1.6

MITSUBISHI CEMENT CORPORATION
Cushenbury plant

Tom Gepford Quality Control Manager



MITSUBISHI CEMENT CORPORATION

CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 12/8/2016

ASTM designation: C 1157 – 11 for Type HE. Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 11/1/2016

To: 11/22/2016

Additional Data

Limestone Addition

% Addition:	12.2
SiO2 (%)	3.5
Al_2O_3 (%)	1.0
Fe_2O_3 (%)	0.3
CaO (%)	51.6
SO ₃ (%)	0.0

Base Cement Phase Composition

C_3S	53
C_2S	20
C_3A	12
C_4AF	3

We certify that the above described data represents the material used in the cement manufactured during the production period indicated.

MITSUBISHI CEMENT CORPORATION
Cushenbury plant

Tom Gepford Quality Control Manager