

CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 03/13/2025

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 02/10/2025

To: 02/27/2025

Chemical Composition:	ASTM Limits	UBC Limits	Test Results
Silicon Dioxide (SiO ₂), %			18.7
Aluminum Oxide (Al ₂ O ₃), %			5.0
Ferric Oxide (Fe ₂ O ₃), %			1.2
Calcium Oxide (CaO), %			64.0
Magnesium Oxide (MgO), %			2.4
Sulfur Trioxide (SO ₃), %			3.3
Loss on Ignition, %		7.0 Max.	5.5
Insoluble Residue, %		1.5 Max.	1.2
Total Alkali (%Na2O + 0.658 * %K2O), %			0.47
Tricalcium Silicate (C ₃ S), [b] %			47
Tricalcium Aluminate (C ₃ A), [b] %			11
CO ₂ , %			4.8
Limestone, %	15 Max.		11.8
Limestone Purity, %		85 Min.	94
Free Lime, %			1.0
PHYSICAL RESULTS:			
Blaine Fineness Average (m²/kg)			530
325 Mesh (% Passing)			98.3
Autoclave Expansion (%)	0.80 Max.		0.08
Mortar Bar Expansion (%)	0.020 Max.		0.008
Time of Set Initial Vicat (minutes)	45 / 420 Min. /	Max	90
Air Content (% by Volume)	12 Max	22 Max.	8.2
C1702 Heat of Hydration (J/g)	(a)		389
Color (L value)	(a)		75
Compressive Strength Test:	ASTM Limits MPA psi		MPA PSI
1 Day		Ain.	21.8 3170
3 Day		Ain.	34.1 4950
7 Day			39.2 5680
28 Day Jan 2025			45.3 6580

This cement has been sampled and tested in accordance with ASTM standard methods and procedures. All test results are certified to comply with the type specification designated above. No other warranty is made or implied. We are not responsible for improper use or workmanship. The MCC laboratory is AASHTO accredited. [a] For information only. [b] Adjusted per ASTM C150 A1.6

MITSUBISHI CEMENT CORPORATION Cushenbury plant

> Evan Coss Quality Control Manager



CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 03/13/25

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 02/10/2025

To: 02/27/2025

Additional Data

Limestone Addition

% Addition:	11.8
SiO2 (%)	2.4
Al_2O_3 (%)	0.8
Fe_2O_3 (%)	0.3
CaO (%)	50.8
SO ₃ (%)	0.1

Base Cement Phase Composition

C_3S	54
C_2S	18
C_3A	12
C ₄ AF	4

We certify that the above described data represents the material used in the cement manufactured during the production period indicated.

MITSUBISHI CEMENT CORPORATION Cushenbury plant

Evan Coss Quality Control Manager