

CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 11/20/2023

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 10/09/2023

To: 10/30/2023

Chemical Composi	ition:	ASTM Limits	UBC Limits	Test Results
Silicon Dioxide (SiO2), %				19.5
Aluminum Oxide (Al ₂ O ₃)	, %			5.2
Ferric Oxide (Fe ₂ O ₃), %				1.1
Calcium Oxide (CaO), %				64.2
Magnesium Oxide (MgO), %				2.0
Sulfur Trioxide (SO ₃), %				3.4
Loss on Ignition, %			7.0 Max.	5.5
Insoluble Residue, %			1.5 Max.	0.9
Total Alkali (%Na ₂ O + 0.658 * %K ₂ O), %				0.45
Tricalcium Silicate (C ₃ S),	[b] %			48
Tricalcium Aluminate (C	3A), [b] %			11
CO ₂ , %				3.8
Limestone, %		15 Max.		9.5
Limestone Purity, %			85 Min.	92
Free Lime, %				1.3
PHYSICAL RESU	JLTS:			
Blaine Fineness Average	(m^2/kg)			541
325 Mesh (% Passing)				99.0
Autoclave Expansion (%)		0.80 Max.		0.10
Mortar Bar Expansion (%	(o)	0.020 Max.		0.010
Time of Set Initial Vicat (minutes)		45 / 420 Min. /	Max	60
Air Content (% by Volun	ne)	12 Max	22 Max.	8.5
C1702 Heat of Hydration	(J/g)	(a)		415
Color (L value)		(a)		78
Compressive Stren	igth Test:	ASTM Limits MPA psi		MPA PSI
1 Day			Ain.	21.7 3140
3 Day			Ain.	32.7 4740
7 Day			•	36.8 5340
	Sept 2023			46.0 6670

This cement has been sampled and tested in accordance with ASTM standard methods and procedures. All test results are certified to comply with the type specification designated above. No other warranty is made or implied. We are not responsible for improper use or workmanship. The MCC laboratory is AASHTO accredited. [a] For information only. [b] Adjusted per ASTM C150 A1.6

MITSUBISHI CEMENT CORPORATION Cushenbury plant

> Evan Coss Quality Control Manager



CERTIFICATE OF TEST

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 11/20/2023

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 10/09/2023

To: 10/30/2023

Additional Data

Limestone Addition

% Addition:	9.5
SiO2 (%)	4.3
Al_2O_3 (%)	1.4
Fe_2O_3 (%)	0.5
CaO (%)	51.1
SO ₃ (%)	0.2

Base Cement Phase Composition

C_3S	53
C_2S	19
C_3A	12
C_4AF	3

We certify that the above described data represents the material used in the cement manufactured during the production period indicated.

MITSUBISHI CEMENT CORPORATION Cushenbury plant

Evan Coss Quality Control Manager