

# **CERTIFICATE OF TEST**

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 11/19/2024

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 10/08/2024

To: 10/26/2024

<b>Chemical Composition:</b>	ASTM Limits	<b>UBC</b> Limits	<b>Test Results</b>
Silicon Dioxide (SiO <sub>2</sub> ), %			19.3
Aluminum Oxide (Al <sub>2</sub> O <sub>3</sub> ), %			5.2
Ferric Oxide (Fe <sub>2</sub> O <sub>3</sub> ), %			1.2
Calcium Oxide (CaO), %			63.1
Magnesium Oxide (MgO), %			2.4
Sulfur Trioxide (SO <sub>3</sub> ), %			3.3
Loss on Ignition, %		7.0 Max.	5.5
Insoluble Residue, %		1.5 Max.	1.2
Total Alkali (%Na <sub>2</sub> O + 0.658 * %K <sub>2</sub> O), %			0.50
Tricalcium Silicate (C <sub>3</sub> S), [b] %			49
Tricalcium Aluminate (C <sub>3</sub> A), [b] %			11
CO <sub>2</sub> , %			3.9
Limestone, %	15 Max.		9.6
Limestone Purity, %		85 Min.	92
Free Lime, %			1.0
PHYSICAL RESULTS:			
Blaine Fineness Average (m²/kg)			540
325 Mesh (% Passing)			98.8
Autoclave Expansion (%)	0.80 Max.		0.10
Mortar Bar Expansion (%)	0.020 Max.		0.008
Time of Set Initial Vicat (minutes)	45 / 420 Min. / 1	Max	60
Air Content (% by Volume)	12 Max	22 Max.	<b>8.7</b>
C1702 Heat of Hydration (J/g)	(a)		360
Color (L value)	(a)		75
<b>Compressive Strength Test:</b>	ASTM Limits MPA psi		MPA PSI
1 Day	1	Iin.	20.8 3010
3 Day		Iin.	32.0 4640
7 Day			36.9 5350
28 Day Sept 2024			44.3 6430

This cement has been sampled and tested in accordance with ASTM standard methods and procedures. All test results are certified to comply with the type specification designated above. No other warranty is made or implied. We are not responsible for improper use or workmanship. The MCC laboratory is AASHTO accredited. [a] For information only. [b] Adjusted per ASTM C150 A1.6

MITSUBISHI CEMENT CORPORATION Cushenbury plant

> Evan Coss Quality Control Manager



# **CERTIFICATE OF TEST**

Source: Cushenbury Plant Limestone Modified Portland Cement - Block Date: 11/19/2024

ASTM designation: C 1157 – 11 for Type HE Production Period

UBC Standard: Section 21.303.1 Vol. 3 From: 10/08/2024

To: 10/26/2024

# **Additional Data**

### **Limestone Addition**

% Addition:	9.6
SiO2 (%)	5.0
$Al_2O_3$ (%)	1.0
Fe <sub>2</sub> O <sub>3</sub> (%)	0.3
CaO (%)	51.0
SO <sub>3</sub> (%)	0.1

# **Base Cement Phase Composition**

$C_3S$	54
$C_2S$	18
$C_3A$	13
C <sub>4</sub> AF	4

We certify that the above described data represents the material used in the cement manufactured during the production period indicated.

MITSUBISHI CEMENT CORPORATION Cushenbury plant

**Evan Coss Quality Control Manager**